


MAXIMUM TORQUE NOT TO EXCEED 15,000 FT-LBS.  
ULTIMATE CAPACITY IS 150 KIPS BASED ON A CAPACITY TO  
TORQUE RATIO OF  $k_t = 10 \text{ FT}^{-1}$

3" X 0.313" W.T. SQUARE TUBE HELICAL LEADS & EXTENSIONS



- NOTES:
1. SHAFT TO MEET OR EXCEED REQUIREMENTS OF ASTM A500 GRADE B/C.
  2. PLATE STEEL TO MEET OR EXCEED REQUIREMENTS OF ATSM A572, GRADE 50.
  3. ALL HELICES ARE FORMED BY PRESS DIE. LEADING EDGE OF HELICES ARE TAPERED TO IMPROVE INSTALLATION CAPABILITIES.
  4. HELIX SPACING IS THREE (3) TIMES THE DIAMETER OF THE LOWER HELIX. SPACING OF LEADING HELIX ON FLIGHTED EXTENSIONS IS THREE (3) TIMES THE DIAMETER OF THE LAST HELIX ON THE PRECEDING SHAFT.
  5. STANDARD HELIX DIAMETERS ARE 8", 10", 12", & 14". STANDARD HELIX THICKNESS IS 1/2".
  6. ALL WELDING TO BE PERFORMED BY CERTIFIED WELDOR IN ACCORDANCE WITH AWS D1.1 STRUCTURAL WELDING CODE - STEEL.
  7. HOT DIP GALVANIZING PER ASTM A153/ASTM A123 [G] OR ZINC PLATING PER ASTM B633 Fe/Zn TYPE III [Z]. BARE STEEL IS ALSO AVAILABLE.
  8. (1) 7/8" DIAMETER X 4 1/2" LONG GALVANIZED HEAVY HEX BOLT ASTM A325 (GRADE 5) AND (1) 7/8" GALVANIZED HEAVY HEX NUT ASTM A194 (GRADE 2H).
  9. HELICAL PILE ASSEMBLIES MANUFACTURED IN ACCORDANCE WITH ICC-ES AC358 ACCEPTANCE CRITERIA FOR HELICAL FOUNDATION SYSTEMS AND DEVICES.
- IDEAL PART # ABBREVIATIONS:
- SQ = SQUARE TUBE  
300 = SHAFT WIDTH  
313 = SHAFT WALL THICKNESS  
EXT = EXTENSION  
FE = FLIGHTED EXTENSION  
SH, DH, TH, QH = SINGLE, DOUBLE, TRIPLE, OR QUAD. HELIX  
[L] = SHAFT LENGTH IN FEET (EXAMPLE: 7' = 7)  
[D] = HELIX DIAMETER(S) IN INCHES (EXAMPLE: 10" = 10)  
X = X (SEPARATES HELIX DIAMETER(S) AND HELIX THICKNESS)  
[T] = HELIX THICKNESS (EXAMPLE: 1/2" = 12)  
[G] = GALVANIZED  
[Z] = ZINC PLATED

DRAWN AP	4/21/2020			PROPRIETARY AND CONFIDENTIAL THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF IDEAL MANUFACTURING, INC. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT WRITTEN PERMISSION OF IDEAL MANUFACTURING, INC. IS PROHIBITED.	
CHECKED DSS	4/22/2020				
IDEAL MANUFACTURING, INC. 999 PICTURE PARKWAY WEBSTER, NY 14580 800-789-4810   WWW.IDL-GRP.COM		SIZE B	DWG NO SQ300313	REV 0	SHEET 1 OF 1
NOT TO SCALE ALL UNITS IN INCHES U.N.O.					